

JOB/TASK: Pick Up and Return of Pallets and Tiles

JOB SAFETY ANALYSIS:

SITE 05.00

SUPERCEDES: New CLIENT NAME & ADDRESS: EQUIPMENT/TOOLS REQUIRED: Communication (Mobile Phone) Witches Hats Lifting Bar / Slings						
			Analysis / Revised by: V Babich, P McSwain, J Payne			
			Permits / Competencies Required: National Construction Safety Awareness Card, Site Safety Manual, High Risk License Class CV PERSONAL PROTECTIVE EQUIPMENT REQUIRED: Above PPE to be available and worn as per site requirement			
						RIS
No	JOB/TASK STEP	POTENTIAL HAZARDS	INITIAL RISK LEVEL	SAFE WORK / CONTROL MEASURES	FINAL RISK LEVEL	
1	Job Planning	 Equipment failure Incorrect address Inspection by regulators Site emergencies 	M	 Prior to first pick up of each day, complete Pre-Start Checklist for truck, lifting gear and crane as per manufacturers' handbook (documented proof recommended) Check lot number against documentation Ensure all tickets and licenses are in possession of driver Carry mobile phone in pocket while on site 	L	
2	Arrival at site	 Traffic / parked vehicles Breach of site requirement Site activities Mobile plant Site hazards 	M	 If unable to park in preferred location, park truck where it is safe and will not obstruct traffic Approach other vehicle owners and request their cooperation If there is a site office report to it for site instructions or read site signage for PPE requirement Read site Safety board and follow site rules Do not approach operating mobile plant without direct signal of driver Conduct and record Site Safety Report before loading on each site 	L	

DATE: 19/04/2013



JOB SAFETY ANALYSIS:

SITE 05.00

JOI	JOB/TASK: Pick Up and Return of Pallets and Tiles			DATE: 19/04/2013		
3	Park truck adjacent to pallets	 Mobile Plant Power lines Vehicles / traffic flow Striking buildings or equipment with boom or load Stability of truck 	Н	 Liaise with any operator of mobile plant Do not extend boom within 3 metres of power lines Use cones around truck if truck protrudes on to road Advise other workers or residents who may be interrupted Inspect site for clearance for boom Truck must be parked on firm ground, apply hand brake, use wheel chocks if parked on a hill, disengage driving gear, activate outriggers 	M	
4	Check site for Tiles and Pallets	 Pallets breaking during lift Fibre boards not stacked correctly packed Sprains and strains Splinters 	IVI	 Ensure pallets are not damaged Boards to be stacked neatly underneath top pallet Stacks of pallets not to exceed 14 pallets high Remove loose boards before lift Performing stretching exercises at start of day and after long periods of driving or inactivity Wear gloves 		
5	(If tiles are to be collected) Stack tiles on to pallets and wrap with plastic	Hand injury Snakes and spiders	M	Wear gloves Take care not to catch hand when stacking against other tiles Inspect area before moving pallets and tiles	L	
6	Lift pallets on to truck	 People in area of boom swing Dropping pallets / Lifting gear failure Swinging Load Load and vehicle stability Crush injuries 	Н	 Operate controls from same side of truck as load Keep constant watch and warn people to stay out of way All lifting gear to comply with OHS Regulations Visually check crane and lifting before and during each use Consider use of a tag line Only lift the load as high as necessary to get it onto truck Load to be spread evenly on tray Do not place hands between load and truck tray or load 	M	
6	Remove lifting gear and store Hiab	Damage to equipment or loose gear Traffic	IVI	Correctly store crane and equipment on truck Retract outriggers If you are going onto road check for traffic first .	L	



CITE OF OO

		JOB SAFE	TY ANALY	2 2: 3	HE U5.UL
JO	JOB/TASK: Pick Up and Return of Pallets and Tiles			DATE: 19/04/2013	
7	Secure Load	Falls from truck tray Lose of load	Н	 Maintain 3 points of contact when climbing up or down Load to be secured by a competent person Laterally and longitudinally 	М
8	Leave site	Loss of equipment Vehicle accident	L	Collect all traffic cones Drive to road conditions	N
9	Arrive at factory	 Pedestrians / traffic Site congestion Mobile plant Site emergency 	Н	 Do not exceed 5 kph on site Park in designated pallet return area Look out for mobile plant and vehicles when out of truck Report to Despatch Office on arrival 	М
10	Remove load restraint and prepare for unloading	 Damage to equipment Mobile plant 	н	 Raise crane out of way Undo and store all load restraint straps Do not approach operating forklift unless drivers signals "C 	ok" M
11	Lower crane and depart site	Pedestrians and traffic	Н	1. Do not exceed 5 kph	М
Rev	riewed by:	22/1./2	L		· · · · · · · · · · · · · · · · · · ·

Rod Gorfinge, Operations Manager

Vic Babich, Divisional Manager



JOB SAFETY ANALYSIS:

SITE 05.00



ALL
ACCIDENTS
NO MATTER
HOW MINOR
MUST BE
REPORTED
TO YOUR
SUPERVISOR














, (print name)	confirm that I have read and been instructed in Job Safety Analysis number				
SITE 05.00 and agree that all the hazards have been identified and the risks reduced to as low as reasonably practicable					
C'arra a dia	Data				
Signed:	Date:				